



# NASHOBA REGIONAL SCHOOL DISTRICT

Robert Frieswick, Facilities Director

FACILITIES DEPARTMENT

50 MECHANIC STREET, BOLTON, MA 01740

Office: 978-779-0539 Cell: 978-990-0264

[frieswick@nrsd.net](mailto:frieswick@nrsd.net)

Date: June 15, 2020

## 2.0 STORAGE TANK CLOSURE AND/OR REMOVAL

### **Addendum #1**

The items listed below shall be considered as part of the Contractor's full scope of work and included in the prices given. The Addendum shall be noted on the Contractor's Bid Form.

- 1) The work shall start prior to June 30, 2020. Work will need to be completed prior to August 10, 2020.
- 2) A construction safety fence (snow fence is allowed) to be placed around the entire perimeter of the work site.
- 3) Removal and replacement of existing fencing will be required to access the AST area.
- 4) The Contractor to cover existing drainage catch basin, with spill containment material (spill socks), located toward the field prior to starting the project. Removal of the spill containment material is required once the project is completed.
- 5) Piping was determined to be double walled flex piping.
- 6) An air pressure test for tightness of both the product and return lines from the vault to the furnace room shall be completed on the primary lines only. The secondary pipe does not require testing.
- 7) The only interior work (basement furnace room) will include the disconnection of the fuel lines for testing and cleaning purposes (both suction and return lines to be tested).
- 8) There will be no asphalt replacement with regards to this portion of the project.
- 9) For bidding purposes estimate the amount of contaminated soil generated during the AST removal at 30 cubic yards. Pricing will be adjusted as necessary.
- 10) If dewatering is required assume the rental period of the fractionation tank is 2 weeks.
- 11) The tank and vault shall be cleaned prior to dismantling the vault structure so as not to create any release from these areas.